MARYLAND HISTORICAL TRUST NR Eligible: yes DETERMINATION OF ELIGIBILITY FORM

no

Property Name: St. John's Lutheran Church	Inventory Number:	G-V-A-058
Address: Garrett Highway Rt. 2 Box 159	Historic district:	yes X no
City: Oakland Zip Code: 21550	County: Garret	rt
USGS Quadrangle(s): Table Rock MD/WV		
Property Owner: St. John's Lutheran Church	Tax Account ID Number	c
Tax Map Parcel Number(s): 26 Tax Map Number	er: 95	
Project: Roth Rock Wind Power Project; Garrett Co. Agency	: MD Public Service	Commission
Agency Prepared By: Paula S. Reed and Associates, Inc.		
Preparer's Name: Merry Stinson	Date Prepared:	1/6/2006
Documentation is presented in: MIHP# G-V-A-058, Maryland Coal Region History	oric Sites Survey, 1981	
Preparer's Eligibility Recommendation: Eligibility recommended	X Eligib	pility not recommended
Criteria: A B C D Considerations: A B	BCD _	EFG
Complete if the property is a contributing or non-contributing resource	to a NR district/proper	ty:
Name of the District/Property:		
Inventory Number: Eligible: yes	Listed:	yes
Site visit by MHT Staff yes X no Name:		Date:
Description of Property and Justification: (Please attach map and photo)		
St. John's Lutheran Church is built in a T-shape, with an entrance tower in the nort on a basement that is rusticated concrete block in some sections, and uncoursed sto arched stained glass windows. Slate covers the roof, and vinyl siding sheathes the varvey in 1981, the first church was built on this property in 1820, replaced by a se built in 1903. The cemetery is located west of the church. The 1981 Maryland Coappears similar to St. John's Lutheran Church in Cumberland.	one elsewhere. The build walls. As noted by in the econd building in 1864.	ding features Gothic- e MHT Coal Region The current church was
Evaluation:		
This church is not associated with local events that have made a significant contrib significant persons of the past. While the church has been associated with the Luth available documentation that suggests that it was particularly significant individual There is also no available documentation that the church building is representative local, regional or national history (Criterion B). It is the third church building on the	eran citizens of the Redl lly in the community's hi of the lives of any indiv	house area, there is no istory (Criterion A). viduals important in
MARYLAND HISTORICAL TRUST REVIEW		
Eligibility recommended Eligibility not recommended		
Criteria: A B C D Considerations: A	_BCD	EFG
MHT Comments:		
Reviewer Office of Preservation Services	6/26/06 Date 28/06	
Reviewer, National Register Program	Date	

200601643

G-V-A-058

St. John's Lutheran Church

Page 2


founding or founders of the community. While it retains its original form, roofing material and windows, the application of vinyl siding, trim and soffits alters the exterior character and diminishes visual integrity. Therefore the church is recommended as not individually eligible for the National Register. With its general form, design and setting intact, and its prominent location near the Redhouse intersection, however, it contributes to a potential Redhouse National Register Historic District.

Archaeological assessment, Criterion D, was not a part of this evaluation of above-ground resources.

History/Context:

Redhouse developed at the intersection of the Northwestern Turnpike (U.S. Route 50) and the Great Warrior's Path (U.S. Route 219). In about 1832 a two-story frame inn was built at this junction, on the property now occupied by G-V-A-43, the Benjamin F. Knepp Barn, on the southeast corner of the intersection. The red-painted "Red House" tavern and the surrounding hamlet served stagecoaches, covered wagons, settlers, cattle drovers, and other travelers at the busy intersection. The tavern property included a drovers' pasture for use by patrons' herds. Also near the intersection was a tollgate for the turnpike, the only one for the Northwestern Turnpike in Maryland. The original tavern operator was Frederick C. Carstens, who sold the Red House to Peter Then the B & O Railroad made its way through Oakland about eight miles to the north in 1852. Eventually the railroad superseded the highways' freight-hauling function and wagons and drovers dwindled at the Redhouse intersection. Peter Shirer sold the Red House to Jacob Swartzentruber in 1855, who owned it through the Civil War. During the war, soldiers confiscated livestock and forage from the tavern and from surrounding farms. The next owner was Christian Martin who demolished the tavern, and in 1890 transferred the property to his son-in-law William Knepp. In the 1920s, Benjamin Knepp, William's son, acquired the property. Benjamin Knepp removed the house that Christian Martin built and constructed the current dwelling on the property, a stone gambrel-roofed house. He also built the gas station in the northwest corner of the Redhouse intersection, G-V-A-045. Adjacent to the gas station stands the Redhouse school and next to it is St. John's Church, an integral part of the crossroads community. Although the present church building dates from 1903, the original Lutheran church on the site was built in 1820, before the tavern and turnpike were constructed.

MARYLA	ND HISTO	ORICAL	TRUST	REVI	EW							
Eligibility	recommen	ded		Eli	igibility not recommen	ded						
Criteria:	A	В	C	D	Considerations:	A	В	C	D	E	F	G
MHT Con		er, Offic	e of Pres	servatio	on Services			Date				
-	Revie	wer, Na	tional R	egister	Program			Date				





G.V.A.058 St. John's Lutheran Church Garrett Co. MD Merry Stinson B/24/05 MD SHPO SWaSE elev.s 10f3



G-V-A 058 St. John - Lutheron Church Garrett Co., MD Paula Reed 4/06 MDSHPO SW VIRW 20+3



G-V-A-058 St. Johns Lutheran Church Garrett Co., MD Paula Reed 4/06 MOSHPO NE view, Church and cemetery 30f3

St. John's Lutheran Church Redhouse Private

1903

St. John's Lutheran Church, built in 1903, is situated at an elevation of 2500 feet at the southern end of Pleasant Valley. It is a frame gable roofed church based on an asymmetrical T-plan. The wing of the "T" is offset on the facade (SE elevation) by a square tower with a steeply pitched pryamidal roof that flares outward at the eaves. A gable-roofed altar projection extends from the center of the rear, northwest elevation.

INVENTORY FORM FOR STATE HISTORIC SITES SURVEY

NAME				
HISTORIC				
AND/OR COMMON				
	Lutheran Church			
LOCATION				
STREET & NUMBER				
	west side, near inter	section with Route	50	
CITY, TOWN			CONGRESSIONAL DIST	RICT
Redhouse		VICINITY OF	6th COUNTY	
Ma	aryland			rett County
CLASSIFIC	ATION			
CATEGORY	OWNERSHIP	STATUS	PRES	SENT USE
DISTRICT	PUBLIC	X OCCUPIED	AGRICULTURE	MUSEUM
∠BUILDING(S)	∠ PRIVATE	UNOCCUPIED	COMMERCIAL	PARK
STRUCTURE SITE	BOTH PUBLIC ACQUISITION	WORK IN PROGRESS ACCESSIBLE	EDUCATIONAL ENTERTAINMENT	PRIVATE RESIDENCE
OBJECT	_IN PROCESS	XYES: RESTRICTED	GOVERNMENT	SCIENTIFIC
	BEING CONSIDERED	YES: UNRESTRICTED	_INDUSTRIAL	_TRANSPORTATION
		NO	MILITARY	OTHER
OWNER O	FPROPERTY			
NAME			Telephone #:	
STREET & NUMBER			rerephone #:	
CITY, TOWN		VICINITY OF	STATE,	zip code
LOCATION	OF LEGAL DESCR		7:1	
COURTHOUSE.			Liber #: Folio #:	
REGISTRY OF DEEDS,	ETC. Garrett County	Courthouse	FOITO #:	
STREET & NUMBER	nird and Alder Streets			
CITY, TOWN	and Aidel Streets		STATE	-
Oa	akland		Mar	yland 21550
REPRESEN	TATION IN EXIST	ING SURVEYS		
TITLE				
- The state of the	one			
DATE		FEDERAL _	STATECOUNTYLOCA	L
DEPOSITORY FOR SURVEY RECORDS				
CITY, TOWN			STATE	



G-V-A-058

CONDITION

CHECK ONE

CHECK ONE

_EXCELLENT

__DETERIORATED

__ALTERED

MOVED DATE......

__FAIR

__UNEXPOSED

DESCRIBE THE PRESENT AND ORIGINAL (IF KNOWN) PHYSICAL APPEARANCE

St. John's Lutheran Church, built in 1903, is situated at an elevation of 2500 feet at the southern end of Pleasant Valley. It is a frame gable roofed church based on an asymmetrical T-plan. The wing of the "T" is offset on the facade (SE elevation) by a square tower with a steeply pitched pryamidal roof that flares outward at the eaves. A gable-roofed altar projection extends from the center of the rear, northwest elevation.

The main entrance into the church is through the tower. The door is covered by a Gothic arch door hood that flares outward at the eaves and is supported by diagonal braces. The door has a Gothic arch stained glass transom which reads: "St. John's Evangelical Lutheran Church." Another entrance is located on the facade, southwest of the "T" wing. The door has a Gothic arch stained glass transom which reads: "Welcome." The basement can be reached through an entrance on the northeast elevation of the church.

The main block of the church rests on a rusticated concrete block foundation. The wing of the "T" and the altar projection rest on uncoursed stone foundations. The basement, added at a later date, explains for the newer concrete block foundation.

The walls are covered with asbestos shingles and the roof with grey slate shingles. A brick chimney pierces the ridgeline of the wing.

There are 3 large Gothic arch stained glass windows with tracery. Two pierce both gables ends of the main block and the third adorns the gable end facade of the wing. The remaining windows are stained glass lancets. Two small, new windows pierce the southwest elevation of the wing just below the eave line.

A cemetery is located southwest and northwest of the church. The Parsonage (See G-V-A-059) is located northeast of the church.

8 SIGNIFICANCE

G-V-A-058

SPECIFIC DAT	ES 1903	BUILDER/ARCH	HITECT	
21900-	COMMONICATIONS	_INVENTION	POLITICS/GOVERNMENT	_OTHER (SPECIFY)
∠ 1900-	COMMUNICATIONS	_INDUSTRY	POLITICS/GOVERNMENT	
1800-1899	COMMERCE	_EXPLORATION/SETTLEMENT	PHILOSOPHY	TRANSPORTATION
1700-1799	ART	ENGINEERING	MUSIC	THEATER
1600-1699	ARCHITECTURE	EDUCATION	MILITARY	_SOCIAL/HUMANITARIAN
1500-1599	AGRICULTURE	ECONOMICS	LITERATURE	SCULPTURE
1400-1499	_ARCHEOLOGY-HISTORIC	CONSERVATION	_LAW	SCIENCE
PREHISTORIC	ARCHEOLOGY-PREHISTORIC	COMMUNITY PLANNING	_LANDSCAPE ARCHITECTURE	∠ RELIGION
PERIOD	AF	REAS OF SIGNIFICANCE CH	IECK AND JUSTIFY BELOW	

STATEMENT OF SIGNIFICANCE

St. John's Lutheran Church was constructed in 1903. It is similar in design to the St. John's Lutheran Church in Cumberland, Maryland.

G-V-A-058

9 MAJOR BIBLIOGRAPHICAL REFERENCES

Wentz, Abdel Ross. <u>History of the Evangelical Lutheran Synod of Maryland of the United Lutheran Church in America 1820-1920</u>. Harrisburg; Evangelical Press, 1920.

CONTINUE	ON	SEPARATE	SHEET	IF	NECESSARY
----------	----	----------	-------	----	-----------

GEOGRAPHICAL DATA	
ACREAGE OF NOMINATED PROPERTY	
VERBAL BOUNDARY DESCRIPTION	
LIST ALL STATES AND COUNTIES FOR PROPERTIES OVERLAPE	ING STATE OF COUNTY POUNDABLES
LIST ALL STATES AND COUNTIES FOR PROPERTIES OVERLAPP	PING STATE OR COUNTY BOUNDARIES
LIST ALL STATES AND COUNTIES FOR PROPERTIES OVERLAPP STATE COUNTY	PING STATE OR COUNTY BOUNDARIES
STATE COUNTY	PING STATE OR COUNTY BOUNDARIES
	PING STATE OR COUNTY BOUNDARIES
STATE COUNTY STATE COUNTY	PING STATE OR COUNTY BOUNDARIES
STATE COUNTY	PING STATE OR COUNTY BOUNDARIES
STATE COUNTY STATE COUNTY FORM PREPARED BY NAME / TITLE	PING STATE OR COUNTY BOUNDARIES
STATE COUNTY STATE COUNTY FORM PREPARED BY	DATE
STATE COUNTY FORM PREPARED BY NAME / TITLE Donna Ware, Historian	DATE
STATE COUNTY FORM PREPARED BY NAME / TITLE Donna Ware, Historian ORGANIZATION	DATE
STATE COUNTY FORM PREPARED BY NAME / TITLE Donna Ware, Historian ORGANIZATION Maryland Historical Trust/Bureau of Mine	DATE 10-82 TELEPHONE (301) 269-2438
STATE COUNTY FORM PREPARED BY NAME / TITLE Donna Ware, Historian ORGANIZATION Maryland Historical Trust/Bureau of Mine STREET & NUMBER	DATE 25 10-82 TELEPHONE

The Maryland Historic Sites Inventory was officially created by an Act of the Maryland Legislature, to be found in the Annotated Code of Maryland, Article 41, Section 181 KA, 1974 Supplement.

The Survey and Inventory are being prepared for information and record purposes only and do not constitute any infringement of individual property rights.

RETURN TO: Maryland Historical Trust
The Shaw House, 21 State Circle
Annapolis, Maryland 21401
(301) 267-1438





Table Rock, MD-WV USGS 7.5 Minute Series Scale 1:24,000 1948, photorevised 1974

G-V-A-058 St. John's Lutheran Church Route 219, west side, near intersection of Route 50




G-V-A-058 St. John's Lutheran Church Garrett County, MD Donna Ware September 8, 1980 NE elevation



G-V-A-058 St. John's Lutheran Church Garrett County, MD Donna Ware September 8, 1980 SE elevation



G-V-A-058 St. John's Lutheran Church Garrett County, MD Donna Ware September 8, 1980 NW elevation (rear)



058

G-V-A-058 St. John's Lutheran Church Garrett County, MD Donna Ware, September 8, 1980 SE elevation